



NOTES

1. INSERT SHALL BE INSTALLED PRIOR TO CONSTRUCTION ACTIVITY, OR UPON PLACEMENT OF A NEW CATCH BASIN.
2. SEDIMENT SHALL BE REMOVED FROM THE UNIT WHEN IT BECOMES ONE-THIRD FULL.
3. SEDIMENT REMOVAL SHALL BE ACCOMPLISHED BY REMOVING THE INSERT, EMPTYING, AND RE-INSERTING IT INTO THE CATCH BASIN.
4. BELOW INLET GRATE DEVICES SHALL BE PREFABRICATED UNITS SPECIFICALLY DESIGNED FOR INLET PROTECTION AND SHALL REMAIN SECURELY ATTACHED TO THE DRAINAGE STRUCTURE WHEN LOADED WITH SEDIMENT AND DEBRIS TO ONE-THIRD TOTAL CAPACITY.